

AD-A115 679


ARMY ENGINEER DISTRICT LOUISVILLE KY
PIGEON CREEK THREE PUMP STATIONS, EVANSVILLE, INDIANA. LOCAL FL--ETC(U)
MAY 82 V C BOARMAN, A W GOODAKER

F/6 13/2

NL

UNCLASSIFIED

Top 2
AD-A115 679



Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER Unit 2, (Part I)	2. GOVT ACCESSION NO. A115679	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Foundation report, Supplement Unit 2 (Part 1) Pigeon Creek Three Pump Stations, Evansville, IN.	5. TYPE OF REPORT & PERIOD COVERED Final	
7. AUTHOR(s) Boarman, Victor C. for Arnold W. Goodaker	8. CONTRACT OR GRANT NUMBER(s) DAGW27-77-C-0140 (1977-79) DAGW27-78-C-0076 (1978-82)	
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Corps of Engineers Louisville District Louisville, KY 40201	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Corps of Engineers Louisville District ORLCD	12. REPORT DATE 20 May 1982	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)	13. NUMBER OF PAGES 75	
	15. SECURITY CLASS. (of this report)	
	15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	

DISTRIBUTION STATEMENT (of this Report)

proved for public release; Distribution unlimited.

DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)

AD A115679
SUPPLEMENTARY NOTES

KEY WORDS (Continue on reverse side if necessary and identify by block number)

Levee
Pump Stations
Pigeon Creek
Evansville, IN

ABSTRACT (Continue on reverse side if necessary and identify by block number)
This report supplements the prior foundation report on the Evansville, IN, levee. It covers foundation conditions encountered and methods of constructing three pump stations within those conditions.

THIS DOCUMENT IS BEST QUALITY PRACTICABLE.
THE COPY FURNISHED TO DDC CONTAINED A SIGNIFICANT NUMBER OF PAGES WHICH DO NOT REPRODUCE LEGIBLY.

DTIC FILE COPY

DD FORM 1 JAN 73 EDITION OF 1 NOV 68 IS OBSOLETE

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

82 06 16 057

Foundation Report
Supplement No. 2 Volume II
Evansville, Indiana
Local Flood Protection Project
Pigeon Creek Section
Unit 2 (Part I) Pump Stations
Sixth Ave., Dresden St., Delaware St.

Accession For	
NTIS GRARI	
DTIC TAB	
Unannounced	
Justification	
By	
District	
Availability	
Approved	
Dist	
A	23



DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

FOUNDATION REPORT
SUPPLEMENT NO. 2 VOLUME II
EVANSVILLE, INDIANA
LOCAL FLOOD PROTECTION PROJECT
PIGEON CREEK SECTION
UNIT 2 (PART I) PUMP STATIONS
SIXTH AVE., DRESDEN ST., DELAWARE ST.

Foundation Report
Supplement No. 2 Volume II
Evansville, Indiana
Local Flood Protection Project
Pigeon Creek Section
Unit 2 (Part I) Pump Stations
Sixth Avenue, Dresden Street, Delaware Street


Table of Contents


<u>Para. No.</u>	<u>Title</u>	<u>Page No.</u>
	<u>Introduction</u>	
1-01	Location	1 - 1
1-02	Description	1 - 1
1-03	Authority	1 - 2
1-04	Purpose of Report	1 - 2
1-05	Contractor and Contract Supervision	1 - 2
	<u>Foundation Exploration</u>	
2-01	Investigation Prior to Construction	2 - 1
2-02	Investigation During Construction	2 - 1
	<u>Geology</u>	
3-01	Geology of Project Area	3 - 1
3-02	Overburden	3 - 1
3-03	Bedrock	3 - 2

Table of Contents

<u>Para. No.</u>	<u>Title</u>	<u>Page No.</u>
<u>Excavation Procedures</u>		
4-01	Sixth Avenue Pumping Station	4 - 1
4-02	Dresden Street Pumping Station	4 - 1
4-03	Delaware Street Pumping Station	4 - 1
4-04	Dewatering Provisions	4 - 4
4-05	Foundation Preparation	4 - 5
<u>Pile Driving</u>		
5-01	Permanent Piling	5 - 1
5-02	Temporary Piling	5 - 1
<u>Possible Future Problems</u>		
6-01	72" Influent Pipe - Delaware Street	6 - 1
6-02	Earthquake and Coal Mines	6 - 2
Photographs - Sixth Avenue Appendix I		
Photographs - Dresden Street Appendix II		
Photographs - Delaware Street Appendix III		
Boring Data - Delaware Street Appendix IV		
Core Date - Delaware Street Appendix V		
Caissons - Delaware Street Appendix VI		
72" R.C.P. Influent - Delaware Street . . Appendix VII		

Plate 1





PART I - INTRODUCTION

1-01 Location. The local protection project for Evansville, Indiana is located in Vanderburgh County, Indiana on the Ohio River. The city limits extend from points approximately opposite River Mile 784 to Mile 796 miles below Pittsburgh. Completed Unit I, Howell and Knight Township sections serve as protection along the Ohio River and Unit II will serve, when completed, as protection along the left bank of a tributary called Pigeon Creek. This report will cover the foundation conditions and construction of three Pumping Plants which will serve for the disposal of interior drainage during flood periods in the area of Unit II - (Part 1). See Plate No. 1. A previously submitted report for Unit II - (Part 1) Volume I covered the Levee construction along the same reach of protection of which the three plants serve. The construction of the Delaware Street, Dresden Street and Sixth Avenue Pumping Plants marks the completion of the Evansville, Indiana Flood Protection Project called Pigeon Creek Unit II - (Part 1).

1-02 Description. Each Pumping Station consists of a brick faced concrete block building with precast concrete roof units and built-up roofing.

Dresden Street Station has three storm water pumps with 30 inch discharge having a capacity of 31,400 g.p.m. each at 9.8 foot head.

Sixth Avenue Station has two storm water pumps with 30 inch discharge and a capacity of 26,200 g.p.m. each at 21.4 foot static head.

Delaware Street Station has two sewage pumps and three storm water pumps. The sewage pumps have 24 inch discharge and 13,450 g.p.m.

capacity each at 52.0 foot head. The storm water pumps have 60 inch discharge and a capacity of 113,400 g.p.m. each at 15 foot static head.

1-03 Authority. The authorization for this construction is the same as for the Levee construction which is the Flood Control Act approved 28 August 1937. The work covered in this report is a part of the overall flood protection plan for the City of Evansville.

1-04 Purpose of Report. This report has been prepared as a record of foundation conditions encountered during construction as well as a record of procedure used to build on the foundation.

1-05 Contractor and Contract Supervision

1-05.1 Dresden Street & Sixth Avenue Pumping Stations

Contract No. DACW27-77-C-0140

Contractor: J. L. Wilson Co., Inc.
Bloomfield, IN

Awarded: October 1977

Substantially Complete: December 1979

Resident Engineer: Arnold W. Goodaker

Inspection: Victor C. Boarman (Supv.)
Jerry M. Wade
Kenneth R. Haywood

1-05.2 Delaware Street Pumping Station

Contract No. DACW27-78-C-0076

Contractor: Indiana Construction Co., Inc.
Fort Wayne, IN

Awarded: June 1978

Substantially Complete: February 1982

Resident Engineer: Arnold W. Goodaker

Inspection: Victor C. Boarman (Supv.)

Jerry M. Wade

Alva B. Johnson

Kenneth R. Haywood

PART II - FOUNDATION EXPLORATION

2-01 Investigation Prior to Construction. Investigation consisted of field reconnaissance and subsurface investigations. Samples of foundation material were obtained by standard penetration methods, hand augers and undisturbed Denison and Shelby tube samples. Investigations were first started in 1938 with additional investigations being made every few years up to December 1977. Boring locations are shown on Plate No. 18 for Sixth Avenue Station and Plate No. 21 for Dresden Street Station. Boring locations for Delaware Street are on Plate No. 25. Boring data for Dresden Street and Sixth Avenue is on Plate No. 24. Boring data for Delaware Street is shown on Plate Nos. 26 through 29.

2-02 Investigation During Construction. No additional borings were made at Dresden Street or Sixth Avenue sites during construction since the foundations were open cut and relatively shallow.

Additional borings were made at the Delaware Street site by Stoll Evans and Associates from Ann Arbor, Michigan in July 1978 for Indiana Construction Company prior to beginning work as a part of a Value Engineering Study. The Value Engineering proposal was not accepted by the Corps of Engineers but the investigative materials have been included in Appendix IV to supplement borings previously made by the Geotechnical Branch. In addition, eleven cores were obtained as part of the contract obligation by J. E. Hoskins Drilling, Inc. to assist in determining the founding elevation for the 44 caissons that support the station. This information is contained in Appendix V of this report.

PART III - GEOLOGY

3-01 Geology of the Project Area. The project area is located near the end of the Eastern Interior Coal Field, in the wide, alluvial filled Ohio River Valley. This valley was carved out during the preglacial and early glacial period. During the late glacial period, melt water from receding glaciers deposited alluvial fill consisting of sand, gravel, silt and clay in the valley. Bedrock in the project area is correlated with the Upper Pennsylvanian Coal measures which usually consists of successive strata of sandstone, shale and coal.

Bedrock formations at or near surface in the Evansville area include, in ascending order, the Dugger, Shelburn and Patoka Formations, all of Pennsylvania age, the age of the great coal deposits of the Eastern United States. The only coal bed that has been actively mined is the Springfield Coal Member (V) of the Petersburg Formation. The coal is about 250 feet beneath downtown Evansville. The approximate thickness of the coal is 4.0 feet.

3-02 Overburden. The overburden at Dresden Street consisted mostly of lean, gray clay with a thin sand seam at approximate Elevation 365+ which contained a small amount of water.

The overburden at Sixth Avenue was mostly a lean, brown clay. The material at both Sixth Avenue and Dresden Street sites was reused for backfill. At the Delaware Street site, overburden consisted of cinders, brick, wood and other random trash fill down to about Elevation 350. The remainder to

Elevation 330 was a lean, gray, silty clay, ranging from wet and soft to damp and very stiff. Below Elevation 330, the material varied between silty clay to fine to medium silty sand. The material below Elevation 330 was only removed from within the caissons. No part of this overburden was used for backfill. All of this material was deposited in the designated waste disposal area.

3-03 Bedrock. No rock was encountered at either the Dresden Street or Sixth Avenue Pumping Station sites.

Bedrock at the Delaware Street site is a soft fissile shale. Core borings made during construction of the pump plant indicated the presence of a disturbance, a possible fault, in the area of caissons C-7 and D-7. The initial phase of the construction contract was to drill 6-inch core holes and set the foundation grade for the caissons. After 10 borings were made and the core analyzed, the grades for the caissons were as shown on the block diagram, Plate No. 33.

Drilling encountered bedding dipping 5° to 10° in two borings and a 3-foot thick disturbed zone in the shale below the dipping beds in core hole C-6A and C-6. This zone is indicated by soft and broken shales and high core losses in C-6. Below the disturbed zone, bedding is horizontal and the shale is firm. The attached block diagram illustrates a dipping structure of approximately 51° with a strike on top of bedrock extending from near caisson D-7 to caisson A-1. There appears to be little, if any, displacement although no good control bedding was penetrated. Boring C-1 encountered shallow dipping beds in the top 3 feet of bedrock, but did not encounter the

disturbed zone, indicating the disturbed zone is not continuous through the foundation of the Delaware Street Pump Plant. The block diagram makes the supposition that the zone is continuous as the worst case.

PART IV - EXCAVATION PROCEDURES

4-01 Sixth Avenue Pumping Station. Prior to excavation at Sixth Avenue site, temporary shoring was driven to protect the existing Levee. PZ27 sheet piling, in 40 foot lengths, was driven on a line 26 feet from the Levee side face of the structure. See Plate Nos. 18, 19 and 20. The toe of the piling was driven to Elevation 3¹/4. A berm 22 feet wide with a 1¹/₂ to 1.5 H slope was left against the piling during excavation for support. The foundation was then excavated to near grade with a drag line bucket. A small dozer was used for cutting final grade prior to placing the mud mat. No free or running water was encountered. The foundation was firm and dry. See Photo Plates 2, 3 and 4 - Appendix I.

4-02 Dresden Street Pumping Station. Steel sheet pile shoring was also driven at the Dresden Street site. Bracing this piling was considerably more difficult because of the limited space. See Plate Nos. 21 and 22. This foundation was also excavated with a drag line and then cut to final grade with a backhoe. A small amount of water was encountered in a sand seam; however, it was easily controlled by ditches and the foundation itself was firm and relatively dry. See Photo Plate Nos. 5, 6 and 7 - Appendix II.

4-03 Delaware Street Pumping Station. A Government designed sheet piling cofferdam was installed at Delaware Street site from Elevation 360⁺. See Plate No. 23. After the piling was driven and the dewatering system installed, forty four 66-inch diameter caissons were installed to a pre-determined rock elevation. (See Appendix VI). This was done by first

augering a 90-inch diameter hole and installing an 84-inch diameter temporary casing with the bottom of the casing set approximately 2 feet below the top elevation of the permanent caisson. A 72-inch diameter hole was then augered to the top of rock and a 66-inch diameter permanent casing was then seated. A 60-inch diameter rock bit was then used to drill to the established founding elevation. The bottom was then cleaned of all loose material and the caisson filled with concrete to the proper elevation. Twenty four hours later the temporary casing was refilled with sand to Elevation 360. The temporary casing was pulled and reused for another hole. After all forty-four caissons were complete plus one more which had not been located properly (see Plate 32, Appendix VI), the H pile supports for the bracing sets were driven. The cofferdam was then excavated to the elevation of the first bracing set. The set was installed and excavation continued. Three sets of bracing were installed. The excavation was accomplished by clamming, by using a small backhoe and by hand. The progress was very slow because of the limited working space due to the bracing, H pile supports and finally the caissons with protruding re-steel. The cofferdam was excavated to approximately 18 inches below grade, leveled up with about 1.0 feet of gravel and a 6-inch concrete mud mat was placed. The final grade was a blue gray, silty, sandy clay. The material was very stiff. An air spade was used to assist the laborers working with shovels. The final grade was reasonably dry. A few areas contained water which came through the pile sheeting or resulted from rain but the grade was very firm prior to placing mud mat. (See Appendix III for photos).

4-03.1 Excavation for 72" and 78" R.C.P.

Since the invert elevations of the entrance pipes for the Delaware Street station are considerably higher than the subgrade for the building, separate cofferdams were driven for these excavations. The actual as-built invert for the 78" R.C.P. is 344.35. Only one piece of pipe, approximately 6.5 feet long, cut at a 66° angle was needed to tie the existing pipe to the building. After the cofferdam was driven, it was excavated down to top of the existing pipe with a clam bucket. The remainder of the excavation was done by hand. The subgrade was a blue silty clay. The pipe was then installed and aligned. The concrete bedding was placed followed by the connecting collar. The excavation was backfilled with sand to approximately 356⁺. The remainder of the fill was silty clay from borrow area "G".

The actual as-built invert for the 72" R.C.P. is 339.36. Three pieces of pipe, eight feet long, were used to make the connection between the existing pipe and the building. After the cofferdam was installed and excavated, a mud mat was placed over the entire cofferdam bottom. Water was coming from under the existing pipe and through the piling on the northwest corner. Once the pipe was installed, aligned and supported, the concrete bedding and connecting collar were placed. Sand was used to backfill the excavation because of the water problem. There may be as much as 6 or 7 feet of sand over the pipe. The remainder of the fill is a silty clay from borrow "G". The piling was then pulled using a vibratory extractor. The piling under the pipe was, of course, left in place. (See Plate Nos. 34 and 35 - Appendix VII).

4-04 Dewatering Provisions. There were no dewatering systems needed for either Dresden Street or Sixth Avenue Pumping Stations other than very minor ditching and surface pumps.

At the Delaware Street site, an eductor system was installed around the entire perimeter of the cofferdam. A total of forty points approximately 7 to 8 feet on centers were installed. Sixteen piezometers were used to monitor the system on a daily basis. The pumping of the system continued until all concrete work was complete to Elevation 360+ at which time the dewatering system and the cofferdam piling were removed. It was determined that there was no danger of flotation before the sump would flood and if it should later become a danger, the sump could be flooded through the 78-inch and/or 72-inch lines. The dewatering system was adequate for the job. There was little problem maintaining piezometer readings below Elevation 327 except on the northeast side. It was generally believed that water on that side was from trash fill at a much higher elevation and did not constitute a danger of up lift. The only real problem with the dewatering system was a maintenance problem due to high iron content in the water clogging the well points.

There was one boil where water was coming up along the sheet piling between caissons 3F and 4F on the northeast side. This was determined to be due to a pile sheet not driven to rock. A second effort to drive the sheet piling proved to be successful and the water flow was cut off. There was seepage through the piling at approximately 350+ ^{cu} ft the same location afterward which supported the theory of water from the trash

fill. This water was controlled throughout construction by surface pumps in the piling webs inside the cofferdam between the sheet piling and the concrete line.

4-05 Foundation Preparation.

4-05.1 Dresden Street and Sixth Avenue Sites. At these sites, a concrete "mud mat" was placed as soon as possible after the foundation was excavated and graded. No other preparation was necessary since the foundation was in excellent condition (See Photos - Appendix I and II).

4-05.2 Delaware Street. The Delaware Street subgrade is not the load carrying portion of the structure since the structure is supported by caissons. Care was taken, however, to keep the subgrade in as good a condition as possible. It was prepared in sections since there was a great deal of hand work involved. As soon as an area was graded it was covered with a minimum of 1.0 foot of gravel and a 6-inch concrete "mud mat". A "mud mat" was used in lieu of filter cloth to give the contractor a better working surface. No areas were left to deteriorate over night. This subgrade was a very firm silty clay. There was one boil as previously mentioned but once this was controlled there were no other major water problems. (See Photos - Appendix III).

4-05.3 Caissons. The caissons were excavated as previously described in Paragraph 4-03. The subcontractor that did the work was Millgard Corporation from Livonia, Michigan. The founding elevations for the caissons was determined by Loren Christman, a Geologist from

S&I Branch, and others from Geotechnical Branch using core samples taken from ten locations. The log of the cores and actual founding elevations are included in this report in Appendixes V and VI. Almost all the foundations were dry. A few had a very small amount of seepage coming in under the steel casing. None had any water coming up from the bottom. As soon as possible after cleanup, the caissons were filled with concrete, usually within one hour. No caissons were left open to the founding elevation overnight. In some cases, a caisson was excavated to top of rock and left overnight then completed the next day. This occurred when the excavation could not be completed in time to get concrete from the plant the same day. A summary of the caisson logs and final locations are included as a part of this report in Appendix VI. Photographs of caisson bottoms are typical for all (Plate Nos. 9 and 10 - Appendix III).

PART V - PILE DRIVING

5-01 Permanent Piling. There was no permanent piling driven at any of the three sites except for some very short pieces under the paved ditch at Dresden Street.

5-02 Temporary Piling.

5-02.1 Sixth Avenue. Temporary shoring was driven at each of the three sites in order to protect the Levee fill. At Sixth Avenue, the piling was driven on a line 26 feet from the face of the structure. See Plate Nos. 18, 19 and 20. The driving was very difficult and very slow. The contractor was unable to pull the piling with the equipment he had so all the piling was cut off approximately 1.5 feet below grade and left in place.

5-02.2 Dresden Street. Temporary shoring was also driven at Dresden Street. This line of piling was driven approximately 15 feet from the face of the structure. See Plate Nos. 21 and 22. The sheet piling was braced against a battered set of H pile driven 37 feet into the ground and set on 8 foot centers. (See Photos - Appendix II). Seven sets of H pile were left in place. Four sets were poured into the concrete base of the structure. All the rest of the bracing and piling was removed as the backfill progressed.

5-02.3 Delaware Street. A rather elaborate Government designed cofferdam was built at the Delaware Street Pump Station site. (See Plate No. 23). The piling was driven using a vibrating type hammer

(Foster Electric Model 275A). The sheet piling was used as the outside form of the structure. Corrugated sheet metal was tack welded to the inside face of the piling to minimize concrete waste and to allow the piling to be pulled after it was no longer needed. The void between the piling and the corrugated sheeting was filled with river gravel prior to pulling the piling. The only piling left in place is under the '72" pipes.

PART VI - POSSIBLE FUTURE PROBLEMS

6-01 72" Influent Pipe - Delaware Street. Sometime in mid October 1981, 72-inch entrance pipe was discovered to have settled. The most obvious failure was the first joint outside the structure wall. There was approximately a 2-inch offset between the two sections at this joint. A subsequent profile of the pipe invert indicated that the lowest point was actually at the connecting collar between the existing pipe and three sections of new pipe used to connect to the structure. There did not appear to be any serious cracking or pipe failure in any joint except the first one outside the building structure. This was due to the fact that some 2 feet-5 inches of the first section of pipe is embedded in the structure wall and, therefore, could not flex. After monitoring the pipe for nearly two months, it did not appear that any more movement was taking place. There was a constant flow of water through the pipe joints that increased and decreased as the river elevation changed. Engineering Division decided the most economical repair would be to insert a 28 foot long, 66-inch diameter, 3/8-inch thick steel pipe inside the 72-inch pipe and fill the annular space with non-shrink grout. A change order was given to Indiana Construction Company to do the work. They engaged Penetryn System, Inc. from Knoxville, Tennessee to stop the flow of water through the joints by injecting a gel sealer. After this work was successfully completed, Deig Brothers Construction Company subcontracted the installation and grouting of the steel pipe. The steel pipe had to be cut into four pieces and then rewelded in the sump area due to the limiting size of the access hatch. The annular space was filled by pumping approximately 5 yards of 12 bag sand, cement

grout into it. A Master Builders high range fluidifier called L.A.-3 was added to the mix in order to reduce the water cement ratio and thereby minimize shrinkage. A periodic inspection of this pipe might be in order to assure no future settlement occurs. See Plate No. 17 - Appendix III, also Appendix VII.

6-02 Earthquake and Coal Mines. Evansville lies along the northern border of an area in which the possibility of severe earthquake damage exists. Shocks similar to the severity produced by the New Madrid earthquake of 1811 - 1812 would cause much damage. A repeat of the New Madrid would create shocks of intensity VIII (considerable damage even in well built structures).

A large part of downtown Evansville is built over abandoned underground coal mines. The voids left are filled with water, but they are subject to roof collapse which consists of shale in most places. Collapse may eventually lead to the surface and cause damage to surface structures. A large earthquake event could contribute to collapse.

The Delaware Street Pump Plant is located within 1,000 feet of mapped underground mines. It is a possibility that the disturbed zone is more an indication of subsidence as opposed to a fault. The lack of fault gouge, slicken sides, displacement and continuity of disturbance found in rock core indicates some structure other than faulting. Dipping beds at ground surfaces with some disturbance below is more indicative of subsidence.


Mapping done for Special Report 12, titled "Environmental Geology of The

Evansville Area, Southern Indiana", by the Indiana Geological Survey, shows underground mining has taken place directly under the Dresden Street and Sixth Avenue Pump Plants. If any cracks develop in the three structures, the cracks should be monitored for the possibility of subsidence producing such cracking.


Appendix I

Photographs - Sixth Avenue

Pump Station



Sixth Avenue Pump Station Foundation - View East



Sixth Avenue Pump Station Foundation - View South



Southeast Corner of Foundation



Southwest Corner of Foundation



Temporary Shoring for Levee Protection

Appendix II
Photographs - Dresden Street
Pump Station




Northern Half of Foundation



Southeast Corner of Foundation
Brown Silty Clay




East Side of Foundation and
Temporary Shoring and Bracing



Northwest Corner of Foundation


Plate 6




Evensville Flood Protection
DADM 27-77-C-0140
Dresden St. Main Ptg.
Nov. 1978 East

View East
Temporary Shoring
Temporary Water By-Pass
Foundation Rebar Just Prior to Concrete

Appendix III
Photographs - Delaware Street
Pump Station




Installing Caissons - Delaware Street



Installing Bracing for Cofferdam
View West




Caisson Bottom 8-F



Caisson Bottom 8-F

Plate 9



Caisson Bottom 3-A



Caisson Bottom 3-A

Plate 10




North Corner - Partial "Mud Slab" and Caissons



Excavating For "Mud Slab" - East Corner

Plate II



West Corner - Caissons and "Mud Slab"




Excavating For "Mud Slab"
Caissons 3-E and 3-F

Plate 12




Excavating for "Mud Slab" - Northeast Side




Excavating for "Mud Slab" - Northeast Side




Excavating - Northeast Side



Southeast Wall Line - "Mud Slab" and Caissons



Northeast Wall Line



Southwest Wall Line


Plate 15




View Toward East Corner



View Toward South Corner




Northwest Wall Line




72" R.C.P. With 66" Steel Liners Installed



Plate 18



U. S. ARMY



CONCRETE PAVEMENT DETAILS




NOTE:
FOR SECTION OF CONNECTION OF PUMPING STATION
AND DETAILS OF PUMP TO CONNECTION
SEE SHEET NO. 1. FOR PUMP TO BE CONNECTED TO
EXISTING OUTLET STRUCTURE, SEE SHEET NO.
FOR DETAIL OF 16" DIA. AIR VENT, SEE SHEET NO.
FOR DIVERSION @ 3000 GPM, SEE SHEET NO.
A DIVERGENCE TUBE IS PROVIDED BY AN
EXISTING DRAINAGE TUBE INDICATED BY AN
ARROW ON SHEET NO. 1. THE DESIGN LEVEL
IS 1000 FT.


1. PROJECT NUMBER & CONTRACT NUMBER (AMEND NO. 2)	2. DRAWING NUMBER	3. DESCRIPTION
U. S. ARMY ENGINEER DISTRICT, LOUISVILLE DIVISION OF ENGINEERING FLOOD PROTECTION EVANSVILLE, INDIANA PINEY CREEK SECTION - UNIT 2 (PART II) BETH AVALIE PUMPING STATION SITE PLAN AND DETAILS		
4. DATE AS SHOWN	5. DRAWING NUMBER 793-12/3/20	

Plate 19


CORPS OF ENGINEERS



SECTION ON E-E OF PUMPING STATION




U. S. ARMY



Pg 1

TOP OF
DESIGN LINE
E38692



SECTION ON E of Pumping Station (6th Ave.)


FLOOD PROTECTION, EVANSVILLE, INDIANA

J. L. Wilson Co., Inc.

DESIGN of SHEET PILE WALL

DRESDEN ST. PUMP STATION

DACW 27-77-E-0140



STIFF CLAY $q_c = 2 \text{ Ton/SF}$

SHORT TERM

$$\gamma = 120 \text{ psf}$$

$$\gamma' = 65 \text{ psf}$$

$$C = 1000 \text{ psf}$$

$$\phi = 0^\circ$$

LONG TERM

$$\gamma = 120 \text{ psf}$$

$$\gamma' = 65 \text{ psf}$$

$$C = 0$$

$$\phi = 30^\circ$$

$$\delta = 10^\circ$$


$$K_p = 4.20$$

$$K_a = 0.33$$

DESIGN ASSUMPTIONS:

TREAT AS TIED WALL WITH $H = 25'$

Plate 21



U. S. ARMY




Plate 23

CORPS OF ENGINEERS






Plate 24

D-5112	D-5116	ED-5124
None	None	None

D-5112	D-5116	ED-5124
None	None	None



DRESDEN STREET



Appendix IV
Boring Data
Delaware Street
Pump Station





Plate 25















Plate 26

U. S. AIR FORCE

FDC-5131 CONTINUED



FDC-5132 CONTINUED



ME-207, B-1020, B-1021, B-1022, B-1023, B-1024,
PME-2010, PME-2011, 20000, 20001, 20002

U. S. NAVY ENGINEER DISTRICT, NEW ORLEANS

FLOOD PROTECTION EVANSTON, ILLINOIS
PRAIRIE CREEK SECTION - UNIT 2 (PART 1)
BELMONT STREET PRAIRIE CITY AREA
BORING LOGS

793-124187

Plate 27

COPY OF EXHIBIT

MAP 97	
100	
90	
80	
70	✓ <u>0.0000</u>
60	
50	
40	
30	
20	
10	
0	

Dense forest sandy soil clay
very damp, still

Wetland forest water
wet, still

H-651	
170	SL. 100
160	SL. 100 Loamy sand gray sandy clay at edge, moist, mod
150	SL. 100 Medium gray & brown sandy clay at edge, at damp, mod
140	SL. 100 Damp, mod
130	SL. 100 Glossy water @ 0.5' very damp, mod -mod
120	SL. 100 Loamy clay, at wet, mod -mod
110	SL. 100

Detailed description: A vertical geological cross-section diagram. The top is labeled 'HA-885'. A vertical scale on the left indicates depth in meters from 310 to 375. The bottom is labeled 'S.E. 1/4 sec. 12, Twp. 23 N., Range 1 E., Minn.' A legend at the bottom defines symbols: a diagonal line for 'Cl.', a horizontal line for 'Damp - wet', and a dashed line for 'Very damp - wet'. The section shows alternating layers of these features, with thicknesses written next to the lines.

Depth (m)	Lithology	Thickness (m)
310	Cl.	10
320	Cl.	10
320	Damp - wet	10
330	Cl.	10
330	Damp - wet	10
340	Cl.	10
340	Damp - wet	10
350	Cl.	10
350	Damp - wet	10
360	Cl.	10
360	Damp - wet	10
370	Cl.	10
370	Damp - wet	10

HA-886

3.0
2.5
2.0
1.5
1.0
0.5
0.0
0.5
1.0
1.5
2.0
2.5
3.0
3.5
4.0
4.5
5.0
5.5
6.0
6.5
7.0
7.5
8.0
8.5
9.0
9.5
10.0
10.5
11.0
11.5
12.0
12.5
13.0
13.5
14.0
14.5
15.0
15.5
16.0
16.5
17.0
17.5
18.0
18.5
19.0
19.5
20.0
20.5
21.0
21.5
22.0
22.5
23.0
23.5
24.0
24.5
25.0
25.5
26.0
26.5
27.0
27.5
28.0
28.5
29.0
29.5
30.0
30.5
31.0
31.5
32.0
32.5
33.0
33.5
34.0
34.5
35.0
35.5
36.0
36.5
37.0
37.5
38.0
38.5
39.0
39.5
40.0
40.5
41.0
41.5
42.0
42.5
43.0
43.5
44.0
44.5
45.0
45.5
46.0
46.5
47.0
47.5
48.0
48.5
49.0
49.5
50.0
50.5
51.0
51.5
52.0
52.5
53.0
53.5
54.0
54.5
55.0
55.5
56.0
56.5
57.0
57.5
58.0
58.5
59.0
59.5
60.0
60.5
61.0
61.5
62.0
62.5
63.0
63.5
64.0
64.5
65.0
65.5
66.0
66.5
67.0
67.5
68.0
68.5
69.0
69.5
70.0
70.5
71.0
71.5
72.0
72.5
73.0
73.5
74.0
74.5
75.0
75.5
76.0
76.5
77.0
77.5
78.0
78.5
79.0
79.5
80.0
80.5
81.0
81.5
82.0
82.5
83.0
83.5
84.0
84.5
85.0
85.5
86.0
86.5
87.0
87.5
88.0
88.5
89.0
89.5
90.0
90.5
91.0
91.5
92.0
92.5
93.0
93.5
94.0
94.5
95.0
95.5
96.0
96.5
97.0
97.5
98.0
98.5
99.0
99.5
100.0













U.S. ARMY

TOP OF SECOND SHEET THIS AND PAGE PREVIOUS EXTRACT
AND COPY MAY BE DESTROYED.

SEARCHED		INDEXED	
SERIALIZED		FILED	
U. S. DISTRICT ATTORNEY'S OFFICE CITY OF DENVER COLORADO FEDERAL BUREAU OF INVESTIGATION			
 <input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/>		FLOOD PROTECTION EQUITY LINE	
		FEDERAL BUREAU OF INVESTIGATION DENVER FIELD OFFICE - U. S. DEPT. OF JUSTICE FEDERAL BUREAU OF INVESTIGATION DENVER LINE FEDERAL BUREAU OF INVESTIGATION	
<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>		<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	
		70-1214/20	

Plate 28

— CORPS OF ENGINEERS —



21 AUGUST

<u>HA-740 B</u>	
340	50 20 10 0
340	100% Grey, smooth, soft
340	100% Brown tan clay, w/ 5% clayey, medium firm
340	100% Brown tan sandy clay, w/ 5% clayey, soft-firm firm
340	100% Grey, smooth, soft

NA-665	
170	170
160	160
150	150
140	140
130	130
120	120
110	110
100	100
90	90
80	80
70	70
60	60
50	50
40	40
30	30
20	20
10	10
0	0

HA-7488		Date Sheet #7 from copy
100	5	
100	6	
100	7	
100	8	
100	9	
100	10	
100	11	
100	12	
100	13	
100	14	
100	15	
100	16	
100	17	
100	18	
100	19	
100	20	
100	21	
100	22	
100	23	
100	24	
100	25	
100	26	
100	27	
100	28	
100	29	
100	30	
100	31	
100	32	
100	33	
100	34	
100	35	
100	36	
100	37	
100	38	
100	39	
100	40	
100	41	
100	42	
100	43	
100	44	
100	45	
100	46	
100	47	
100	48	
100	49	
100	50	
100	51	
100	52	
100	53	
100	54	
100	55	
100	56	
100	57	
100	58	
100	59	
100	60	
100	61	
100	62	
100	63	
100	64	
100	65	
100	66	
100	67	
100	68	
100	69	
100	70	
100	71	
100	72	
100	73	
100	74	
100	75	
100	76	
100	77	
100	78	
100	79	
100	80	
100	81	
100	82	
100	83	
100	84	
100	85	
100	86	
100	87	
100	88	
100	89	
100	90	
100	91	
100	92	
100	93	
100	94	
100	95	
100	96	
100	97	
100	98	
100	99	
100	100	

NAME		CLASS	GRADE	TELEGRAM
John		1		
John		2		
John		3		
John		4		
John		5		
John		6		
John		7		
John		8		
John		9		
John		10		
John		11		
John		12		
John		13		
John		14		
John		15		
John		16		
John		17		
John		18		
John		19		
John		20		
John		21		
John		22		
John		23		
John		24		
John		25		
John		26		
John		27		
John		28		
John		29		
John		30		
John		31		
John		32		
John		33		
John		34		
John		35		
John		36		
John		37		
John		38		
John		39		
John		40		
John		41		
John		42		
John		43		
John		44		
John		45		
John		46		
John		47		
John		48		
John		49		
John		50		
John		51		
John		52		
John		53		
John		54		
John		55		
John		56		
John		57		
John		58		
John		59		
John		60		
John		61		
John		62		
John		63		
John		64		
John		65		
John		66		
John		67		
John		68		
John		69		
John		70		
John		71		
John		72		
John		73		
John		74		
John		75		
John		76		
John		77		
John		78		
John		79		
John		80		
John		81		
John		82		
John		83		
John		84		
John		85		
John		86		
John		87		
John		88		
John		89		
John		90		
John		91		
John		92		
John		93		
John		94		
John		95		
John		96		
John		97		
John		98		
John		99		
John		100		

Plate 29

**⚠ LABORATORY TEST RESULTS
BONING BC-2000**

DEPTH (F.T.)	INITIAL W.C. (PSI)	DRY DENSITY BEFORE TEST (PCF)	UNCONFINED COMPRESSIVE STRENGTH (PSI)	
			TEST 1	TEST 2
48.0 - 49.0	0.0	128.0	386	
50.0 - 50.5	9.7	116.0	365	
51.0 - 52.0	10.0	130.4	439	
53.0 - 53.4	10.8	110.6	100	
53.5 - 56.0	NOT DETERMINED	128	187	
56.0 - 57	NOT DETERMINED	122.0	36	
58.25 - 59.0	NOT DETERMINED	118.3	78	

NOTE:
ALL BORINGS IN THIS CONTRACT, WITH THE EXCEPTION OF
BC-5000 AND BC-5001, WERE DRILLED PRIOR TO CONSTRUCTION
OF LEVEE.

DC-1100, DC-900

RECEIVED - 1968-08-29 10:00 AM
FBI - BOSTON
SEARCHED INDEXED SERIALIZED FILED



STOLL, EVANS & ASSOCIATES
soil mechanics and foundation consultants

JOB NAME: PUMP STATION

BY: UWS DATE: 7/78 SHEET: A

JOB LOCATION: EVANSCVILLE, INDIANA


SUBJECT: BORING LOCATION PLAN

CLIENT: INDIANA CONSTRUCTION CORPORATION

PROPOSED TEMPORARY RE-CONTOURING

—N—

SCALE: 1" = 40'



LEGEND:

- EXISTING CONTOURS
- - - PROPOSED CONTOURS DURING CONSTRUCTION



STOLL, EVANS & ASSOCIATES
soil mechanics and foundation consultants

JOB NAME: PUMP STATION

BY: UWS DATE: 7/78


Rev. A

JOB LOCATION: EVANSCVILLE, INDIANA

SUBJECT: REVISED TEMPORARY CONTOURING

CLIENT: INDIANA CONSTRUCTION CORPORATION

(MAINTAINING EXISTING LEVEE & ROADS)





STOLL, EVANS & ASSOCIATES
soil mechanics and foundation consultants

JOB NAME: PUMP STATION

BY: UWS


DATE: 7/78

sheet: A-1

JOB LOCATION: EVANSCVILLE, INDIANA

SUBJECT:

CLIENT: INDIANA CONSTRUCTION CORPORATION






STOLL, EVANS & ASSOCIATES
soil mechanics and foundation consultants

JOB NAME: PUMP STATION
JOB LOCATION: EVANSCVILLE, INDIANA
CLIENT: INDIANA CONSTRUCTION CORPORATION

BY: UWS DATE: 7/78 SHEET: A-2
SUBJECT:



STOLL, EVANS & ASSOCIATES
soil mechanics and foundation consultants

JOB NAME PUMP STATION
 JOB LOCATION EVANSCVILLE, INDIANA
 CLIENT INDIANA CONSTRUCTION CORPORATION

BY JAM DATE 7/78 SHEET B-1
 SUBJECT LABORATORY DATA SUMMARY

SAMPLE IDENTIFICATION			LABORATORY DESCRIPTION	NATURAL MOISTURE (%)	DRY DENSITY (PCF)	SHEAR STRENGTH (KSF)
BORING NUMBER	SAMPLE NUMBER	DEPTH (FEET)				
B-B	S-1	6'-6"	SOFT GRAY CLAY FILL	51.41		TV=.2
B-C	S-1	26'	VERY SILTY GRAY CLAY (DISTURBED SAMPLE)	22.38		TV=1.1
B-A	ST-1	5-7'	STIFF BROWN SILTY CLAY WITH SOME GRAY CLAY	17.05		PP=4.2
B-A	ST-2	10 - 12'	BROWN SILTY CLAY WITH DARK CLAY SILTY	19.56		PP=1.8
B-A	ST-4	20 - 22'	STIFF GRAY SILTY CLAY	27.10		PP=2.5
B-A	ST-5	25 - 27'	STIFF GRAY SILTY CLAY WITH BROWN CLAY	25.71		PP=2.45
B-A	ST-6	30 - 32'	STIFF GRAY SILTY CLAY WITH BROWN CLAY	22.06		PP=1.3
B-A	ST-7	35 - 37'	STIFF GRAY SILTY CLAY WITH BROWN CLAYEY FINE SAND &	19.51		PP=1.4
B-B	ST-2	8 - 10'	OLIVE-GRAY MOTTLED SILTY CLAY AND ORGANIC MATTER	32.43		TV=.5 to .74
B-B	ST-3	13 - 15'	STIFF GRAY SILTY CLAY WITH SOME BROWN	23.42		PP=1.7
B-B	ST-4	18 - 20'	GRAY SILT WITH TRACE OF CLAY BINDER	24.0		TV=.9
B-B	ST-5	23 - 25'	SOFT GRAY SILT WITH SOME CLAY BINDER	24.45		PP=2.2
B-B	ST-6	28 - 30'	STIFF GRAY SILTY CLAY WITH SOME BROWN MOTTLING	21.03		PP=1.7
B-B	ST-7	33 - 35'	SOFT GRAY CLAY SAND WITH SILT	23.62		TV=.4
B-B	ST-9	43 -43'4"	VERY STIFF COMPACTED SILT, LITTLE CLAY BINDER & BROWN MOTTLING	13.69		PP=4.5
B-C	ST-1	4 - 5'	BROWN SILTY CLAY	23.65		PP=1.3
B-C	ST-2	8 - 10'	BROWN MOTTLED SILTY CLAY WITH TRACE OF SAND	23.27		TV=.4
B-C	ST-3	13 - 15'	STIFF GRAY SILTY CLAY	26.09		PP=1.9
B-C	ST-4	18 - 20'	SOFT GRAY SILTY CLAY WITH BROWN FINE SAND SEAMS	24.93		PP=2.0
B-C	ST-6	28 - 30'	GRAY FINE TOMED (CLAYEY) SAND (SAMPLE HAD SOME CLAY AT PERIMETER WHICH SUGGESTS DISTURBED SAMPLE)	21.46		

* BASED ON TORVANE SHILAR TEST
OR PENETROMETER TEST



STOLL, EVANS & ASSOCIATES
soil mechanics and foundation consultants

JOB NAME PUMP STATION
JOB LOCATION EVANSTVILLE, INDIANA
CLIENT INDIANA CONSTRUCTION CORPORATION

By PCJ Date 7/78 Sheet B-2
Subject LABORATORY DATA SUMMARY


SAMPLE IDENTIFICATION			LABORATORY DESCRIPTION	NATURAL MOISTURE (%)	DRY DENSITY (PCF)	SHEAR STRENGTH (KSF)
BORING NUMBER	SAMPLE NUMBER	DEPTH (FEET)				
B-D	ST-1	3 - 5'	OLIVE GRAY MOTTLED SILTY CLAY WITH ORGANIC MATTER	28.96		PP = 3.25 to 3.75
B-D	ST-2	8 - 10'	BROWN SILTY CLAY WITH POSSIBLE SILT SEAMS	22.25		PP = 2.25 to 2.35
B-D	ST-3	13 - 15'	GRAY VERY SILTY CLAY (CLAYEY SILT)	25.60		PP = 2.9 to 3.5
B-D	ST-4	18 - 20'	GRAY VERY SILTY CLAY (CLAYEY SILT)	27.69		PP = 1.5
B-D	ST-5	23 - 25'	GRAY VERY SILTY CLAY WITH SILT SEAMS (CLAYEY SILT)	24.94		PP = 1.35 to 1.75
B-D	ST-6	28 - 30'	GRAY SANDY SILTY CLAY	21.28		TV = .72
B-D		30+	GRAY FINE TO MEDIUM SAND			
B-E	ST-1	4 - 6'	BROWN SILTY CLAY WITH SOME SAND (POSSIBLE FILL)	23.21		PP = 1.2 to 1.3
B-E	ST-2	8 - 10'	BROWN-GRAY MOTTLED SANDY SILTY CLAY	24.17		TV = .48
B-E	ST-3	13 - 15'	BROWN-GRAY MOTTLED VERY SILTY CLAY	27.19		PP = 1.0 to 1.25
B-E	ST-4	18 - 20'	GRAY CLAYEY SILT	27.75		TV = .64
B-E	ST-5	23 - 25'	GRAY CLAYEY SILT	28.46		TV = .42 to .56
B-E	ST-6	28 - 30'	OLIVE-GRAY SILTY CLAY WITH SAND	23.56		TV = .78
B-F	ST-1	3 - 5'	BROWN FINE TO MEDIUM SAND WITH SOME SILT	--		--
B-F	ST-4	18 - 20'	GRAY SILTY CLAY WITH TRACE OF SAND	28.00		TV = .56
B-F	ST-5	23 - 25	GRAY CLAYEY SILT	28.14		PP = 1.4
B-F	ST-6	28 - 30'	GRAY CLAYEY SILT	26.74		PP = .9 to 1.0

- * BASED ON TORVANE SHLAR TEST OR PENETRUMETER TEST

STOLL, EVANS & ASSOCIATES
Soil mechanics and foundation consultants

JOB NAME: PUMP STATION
JOB LOCATION: EVANSCVILLE, INDIANA
CLIENT: INDIANA CONSTRUCTION CORPORATION

BY UWS DATE: 7/78 SHEET: B-3
SUBJECT: PARTICLE SIZE DISTRIBUTION
ANALYSIS SUMMARY




C-5-72 2

STOLL, EVANS & ASSOCIATES
soil mechanics and foundation consultants

JOB NAME: PUMP STATION
JOB LOCATION: EVANSCVILLE, INDIANA
CLIENT: INDIANA CONSTRUCTION CORPORATION

BY UWS DATE 7/78 SHEET 8-4
SUBJECT: PARTICLE SIZE DISTRIBUTION
ANALYSIS SUMMARY






STOLL, EVANS & ASSOCIATES
soil mechanics and foundation consultants

JOB NAME PUMP STATION
JOB LOCATION EVANSVILLE, INDIANA
CLIENT INDIANA CONSTRUCTION CORPORATION

BY UWS DATE 7/78 SHEET B-5
SUBJECT PARTICLE SIZE DISTRIBUTION
ANALYSIS SUMMARY



STOLL, EVANS & ASSOCIATES

JOB NAME: PUMP STATION

BY: LV/PCJ DATE: 7/78


JOB LOCATION: EVANSTVILLE, INDIANA

SUBJECT: GRAPHICAL SUMMARY OF TESTS

CLIENT: INDIANA CONSTRUCTION CORPORATION

BORING NO. A SHEET NO. B-6

A SHEET NO. B-6



STOLL, EVANS & ASSOCIATES

JOB NAME: PUMP STATION


BY: LV DATE: 7/78

JOB LOCATION: EVANSCVILLE, INDIANA

SUBJECT: GRAPHICAL SUMMARY OF TESTS

CLIENT: INDIANA CONSTRUCTION CORPORATION

BORING NO. B SHEET NO. 8-7



STOLL, EVANS & ASSOCIATES

JOB NAME: PUMP STATION


BY: LV DATE: 7/78

JOB LOCATION: EVANSTVILLE, INDIANA

SUBJECT: GRAPHICAL SUMMARY OF TESTS

CLIENT: INDIANA CONSTRUCTION CORPORATION

BORING NO. D SHEET NO. 3-8



STOLL, EVANS & ASSOCIATES

JOB NAME: PUMP STATION


BY: LV DATE: 7/78

JOB LOCATION: EVANSCVILLE, INDIANA

SUBJECT: GRAPHICAL SUMMARY OF TESTS

CLIENT: INDIANA CONSTRUCTION CORPORATION

BORING NO. C SHEET NO. 8-9



Appendix V

Core Data

Delaware Street

Pump Station

CONT'D DACW 78-C-0076

Hole No. C-1

DRILLING LOG	DIVISION	INSTALLATION	SHETT OF 2 SHEETS
PROJECT FLOOD PROTECTION EVANSVILLE INDIANA UNIT		ORLCO	
LOCATION (Coordinates or Section)		10. SIZE AND TYPE OF BIT 6" DIAM. RD	
S. W. CORNER OF STRUCTURE		11. DATUM FOR ELEVATION SURVEY (ft. above sea level)	
D. DRILLING AGENCY J. F. HOSKINS DRILLING INC.		12. MANUFACTURER'S DESIGNATION OF DRILL POKTA DRILL	
C. HOLE NO. (As shown on drawing sheet and site number)		13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED N/A UNDISTURBED N/A	
E. NAME OF DRILLER MIKE SCHUBERT		14. TOTAL NUMBER CORE BOXES 3	
F. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED DEG. FROM VERT.		15. DATE HOLE STARTED 18 Oct. 78 COMPLETED 19 Oct. 78	
G. THICKNESS OF OVERTBURDEN 44.2'		17. ELEVATION TOP OF HOLE 360.5 Top Casing	
H. DEPTH DRILLED INTO ROCK 143'		18. TOTAL CORE RECOVERY FOR BORING 100%	
I. TOTAL DEPTH OF HOLE 60.0'		19. SIGNATURE OF INSPECTOR <i>J. F. Hoskins by J. F. Hoskins</i> <i>Laurie A. Christensen</i>	
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS TOP OF (Description)
360.5	0.0	*	Casing
359.0	1.5	*	Top of Ground
348.8	15.7	*	OVB/trash
314.4	5.1	SH	Top of Rock SHALE CLAYEY, bluish gray, soft V. frac. 314.8-314.4 26° dipping beds 314.4, 314.1, 313.6, 313.3, 313.1, 312.5
311.7	48.8		TOP of Firm Rock SHALE CLAYEY mod. h. 1/5 in. seam incl. 5" sa. seams @ 309.6 (C. n.c.) 309.6 308.4 307.9 307.2 316.9 306.6 305.9 305.7 315.3 315.0 304.5 304.1 303.9 303.6 303.0 302.7 302.6 301.3 301.0
305.4	55.1		Box No 1
	56.0		Bedding dipping 26° from 314.8 to 311.7
	57.0		Solid core below 311.7 Cut 4.9' Rock 4.5' left 0.4'
			Box No 2
			Cut 4.9' Rock 4.5' Gain 0.4'
			Box No 3

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 360.5 Top of Hole	Hole No.	C-1	
PROJECT EVANSVILLE INDIANA DELAWARE STREET PUMPING STATION			INSTALLATION OP-1	SHEET	2 OF 2 SHEETS	
ELEVATION 303.5	DEPTH 57.0	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOV. ERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
	58.0				Box No 3	
	59.0					
300.5	60.0		Bottom of Hole			

After coring
Completed hole
was created
back to 330. El.

CONTR NO. DACW 27-78-C-0076

Hole No. C-2

DRILLING LOG	DIVISION	INSTALLATION	SHEET OF / SHEETS		
PROJECT EVANSVILLE FLOOD PROTECTION DELAWARE STREET PUMP PLANT LOCATION (Coordinate or Station)		ORLCI			
CENTER OF WEST SIDE OF STRUCT.		10. SIZE AND TYPE OF BIT 6 1/2" by 5 1/2"			
DRILLING AGENCY J. F. HOSKINS DRILLING INC		11. DAY OR ELEVATION SHOWN (Year)			
HOLE NO. (As shown on drawing No.) and No. numbered		12. MANUFACTURER'S DESIGNATION OF DRILL PORTADRILL 524 J			
NAME OF DRILLER MIKE SCHUBERT		13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN	14. TOTAL NUMBER CORE BOXES		
DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED DEG. FROM VERT.		15. DISTURBED N/A	16. ELEVATION GROUND WATER		
THICKNESS OF OVERBURDEN 45.3'		17. TOTAL CORE RECOVERY FOR BORING	18. COMPLETED		
DEPTH DRILLED INTO ROCK 12.9'		19. SIGNATURE OF INSPECTOR			
TOTAL DEPTH OF HOLE 59.8'		Louna A. Christman			
ELEVATION	DEPTH	CLASSIFICATION OF MATERIALS (Description)	CORE RECOV- ERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
359.3	0.0	00B			
315.0	44.3	Started Coring @ 315.0			Set 4 8" casing to 315.0 prior to coring
314.4	44.9	Top of Rock	100%		M.D.
312.0	45.5	CLAYEY SHALE bl.-gr. m. 1 1/2; h. 0 concr. 30' 5, 6' occ. scattered gr. size incl.	100%		Casing dropped to 314.4 when coring
312.3	47.0	SH			Started when core pulled there was wire in tip of barrel
	48.0	core reduced in size from section 314.0 to 312.3'		Box	Cut 14.9 Top Per'd 14.5 312.3 Loss 0.4'
	49.0				
	50.0				
	51				
	52		100%		
	53			Box	2
	54				
	55	concr. 20. 304.7 - 308.6			
	56				
	302.7			Box	3
302.1	57	clay	CLAYEY SHALE SOFT PLASTIC (creased Mech.) concr. 20. 302.1 - 302.6		
301.6	57.6	SH.	66' 301.6 to 300.5 clean cut bottom		
300.5	59				
299.5	59.6		Solid Core		M.D.

AD-A115 679

ARMY ENGINEER DISTRICT LOUISVILLE KY
PIGEON CREEK THREE PUMP STATIONS, EVANSVILLE, INDIANA. LOCAL FL--ETC(U)
MAY 82 V C BOARMAN, A W GOODAKER

F/6 13/2

NL

UNCLASSIFIED

2 18 2
44-152-12

END
11
7 82
DTIC

CONTR NO. DACW-27-78-0076

Hole No. C-3

DRILLING LOG	DIVISION	INSTALLATION	SHEET / OF / SHEETS			
CONSTRUCTION		ORLCG				
1. PROJECT <u>EVANSVILLE FLOOD PROTECT</u> <u>DELAWARE ST PUMP PLANT</u>		10. SIZE AND TYPE OF BIT <u>6" by 6 7/8"</u>				
2. LOCATION (Coordinates or Section)		11. DAYUM FOR ELEVATION SHOWN (TYPE OF SURF)				
3. DRILLING AGENCY <u>J.E. HOSKINS DRILLING INC.</u>		12. MANUFACTURER'S DESIGNATION OF DRILL <u>MSL</u>				
4. HOLE NO. (As shown on drilling log) and Site Number		13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN	14. DISTURBED			
5. NAME OF DRILLER <u>MIKE SCHUBERT</u>		15. TOTAL NUMBER CORE BOXES	16. UNDISTURBED			
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED DEG. FROM VERT.		16. DATE HOLE STARTED <u>9 Nov.</u>	17. COMPLETED <u>9 Nov. 78</u>			
7. THICKNESS OF OVERTBURDEN <u>45.1</u>		17. ELEVATION TOP OF HOLE				
8. DEPTH DRILLED INTO ROCK <u>151</u>		18. TOTAL CORE RECOVERY FOR BORING				
9. TOTAL DEPTH OF HOLE <u>612</u>		19. SIGNATURE OF INSPECTOR <u>Logg'd by Steven A. Christensen</u>				
ELEVATION 360.9 360.8	DEPTH 0.0 0.6	LEGEND SH.	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOV. •	BOX OR SAMPLE NO. •	REMARKS (Drilling Hole, Sample Log, Depth of overburden, etc., if significant)
				LOSS	1	
315.2		45.1				M.D. 45.1
45.3			CLAYEY SHALE 61-gr m.h.			
96.0		SH.	discont. concr incl grs size 315.0, 314.4, 314.1 concr. 20. 312.8 to 312.7 core pa's @ 311.6, 313.7, 313.2, 312.7, 312.2, 311.6, 310.8			Cut 51 Rec'd 4.9
47.0						LOSS 0.2
48.0			1/2" discont. concr. mod 311.2		Box No 1	
49.0			1/2" " 20.66n 311.0			
310.1		50	1/2" h. concr 20.309.6 309.0 308.2	50.2	C.D. 50.2	" was dropped 0.1"
51			pa's @ 308.2 307.3		Box 2	
52			solid core 307.3 to 304.5			
53				100%	52.9	
54						Cut 88' Rec'd 8.8'
55						
56					55.7	
303.7		56.5	cl. co. partitic. core			
57			core pa's 302.0 301.2			
58				Box 4	58.4	
301.2		59	h. concr incl. 301.3			C.D. 59.0 M.D. 59.0
60			solid core 301.2 to 299.0		Box 5	Cut 2.2' Rec'd 2.2'
299.0		61.2	Bottom of Hole.		61.2	M.D. 61.2

CONTR. DFCW 78-2-0076

Hole No. C-4

DRILLING LOG	DIVISION CONSTRUCTION	INSTALLATION ORL.C.D.	SHET 1 OF 2 SHEETS
1. PROJECT EVANSVILLE DELAWARE STREET PUMP PLANT		10. SIZE AND TYPE OF BIT 6"	
2. LOCATION (Coordinates or Station) CENTER SOUTH SIDE OF STRUCTURE		11. DAY/TIME FOR ELEVATION SURVEY (TYPE OF SURVEY)	
3. DRILLING AGENCY J.E. HOSKINS DRILLING, INC.		12. MANUFACTURER'S DESIGNATION OF DRILL PORTADRILL	
4. HOLE NO. (As shown on drawing file) and site number		13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN	14. DISTURBED N/A
5. NAME OF DRILLER MIKE SCHUBERT		15. TOTAL NUMBER CORE BOXES	16. UNDISTURBED N/A
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED	DEG. FROM VERT.	17. ELEVATION GROUND WATER	
7. THICKNESS OF OVERTBURDEN 46.3'		18. DATE HOLE STARTED 24 Oct 78	COMPLETED 25 Oct 78
8. DEPTH DRILLED INTO ROCK 155'		19. ELEVATION TOP OF HOLE 359.5 - 359.3	
9. TOTAL DEPTH OF HOLE 60.6 From Top Casing 35.2		20. TOTAL CORE RECOVERY FOR BORING 100	
ELEVATION DEPTH LEGEND CLASSIFICATION OF MATERIALS 358.5 0' 0" <i>To Casing at 35.2 Up</i>		21. SIGNATURE OF INSPECTOR Logged By <i>J.E. Hoskins Inc. - J.E. Hoskins</i>	REMARKS (Drilling time, water level, depth of overburden, etc., if applicable)
359.2 45.3 SH Top of Rock CLAYEY SHALE, bl-gr. m.h./sa sc (1/2") sandy top as 313.3 312.2 311.3 308.4 307.8 307.3 306.7 306.4 306.1		LOST	<i>Lost 0.3' setting coring and cleaning of hole prior to coring</i>
50 CONC. incl. 304.8 to 304.9			<i>Cut +5.1' Reid 4.8' Lost 0.3'</i>
51			<i>Measured Depth 50.9'</i>
52 SLS loose 304.0 to 303.8		RUN No 2	<i>Cut 10.2' Reid 10.2'</i>
53			
54 sa. cover lenses @ 301.7 300.6		Box No 2	
55			
56			
57			
58			
59			
60.0		Box No 3	

OVB

Top firm Rock
31402

25 Oct
25 Oct
25 Oct
25 Oct

Measured Depth 60.6

DRILLING LOG (Cont Sheet)				ELEVATION TOP OF HOLE EL. 359.5 Top Casing	Hole No. C-4
PROJECT EVANSVILLE FLOOD PROTECT.		INSTALLATION		SHOT 1 OF 2 SHOTS	
DELAWARE STREET PUMP PLANT OPLCD					
LEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOV- ERY e	BOX OR SAMPLE NO. f
298.7	60.0		Bottom of Hole		Box 4
	60.6				

CONTR. NO. PACW27-78-C-0076

Hole No. C-5

DRILLING LOG		DIVISION CONSTRUCTION	INSTALLATION ORICD	SHET OF / SHEETS 1 / 1
1. PROJECT EVANSVILLE FLOOD PROTECTION		10. SIZE AND TYPE OF BIT 6' 64 67/8"		
DELAWARE STREET PUMP PLANT		11. DATUM FOR ELEVATION BROWN (FEET & INCHES)		
2. LOCATION (Coordinate or Section)		12. MANUFACTURER'S DESIGNATION OF DRILL PORTADRILL 524T		
3. CENTER OF STRUCTURE		13. TOTAL NO. OF OVER- BURDEN SAMPLES TAKEN	DISTURBED N/A	UNDISTURBED N/A
4. DRILLING AGENCY J.E. HOSKINGS DRILLING INC.		14. TOTAL NUMBER CORE BOXES 3		
5. HOLE NO. (As shown on drawing sheet and site number)		15. ELEVATION GROUND WATER		
6. NAME OF DRILLER MIKE SCHUBERT		16. DATE HOLE 300 Oct 78	STARTED 31 Oct 78	COMPLETED
7. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED DEG. FROM VERT.		17. ELEVATION TOP OF HOLE 359.6		
8. THICKNESS OF OVERTURDEN 03 9		18. TOTAL CORE RECOVERY FOR BORING 96%		
9. DEPTH DRILLED INTO ROCK 15.3'		19. SIGNATURE OF INSPECTOR L. J. H. Hosking		
10. TOTAL DEPTH OF HOLE 60.2				
ELEVATION 359.6	DEPTH 0.0	LEGEND SH	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOV. •
				BOX OR SAMPLE NO. #
				REMARKS (Drilling time, water loss, depth of overburden, etc., if applicable)
				<i>set 8" Casing</i>
314.7	44.9	SH	TOP Rock	
			CLAYEY SHALE 61-grn 71.1.1 1/2" SG SCAMS 1 occ. concr. incl. 2a @ average 6" centers 314.7 to	
	46	SH		
	47			<i>Measured Depth. Prior to start of coring</i>
	48			
311.0	46.6			
	49			
308.7	50			
	51			
	52			
	53		CORE SPIN @ 306.4	
	54			
308.2				
	55			
	56			
308.2				
301.8	CLAY		mech. 6kpi. 302.6 to 302.5 CLAY 20.4 CLAY SURF. VARIOUS ND. SH.	
	57			
	58			
	59	SH		
299.4	60			
	60.2		Bottom Hole	<i>Measured Depth.</i>

CONTR. NO. DACW 27-78-C-0076

Hole No. C-6

DRILLING LOG		CONSTRUCTION		INSTALLATION	SHEET OF 1 SHEETS	
PROJECT EVANSVILLE FLOOD PROTECTION DELAWARE STREET PUMP PLANT				ORLC D		
LOCATION (Coordinates or Station)				10. SIZE AND TYPE OF BIT	6" R/M 67F	
B. DRILLING AGENCY <u>J. E. HOSKINS DRILLING INC</u>				11. DATUM FOR ELEVATION SHOWN (TIDE OR MSL)	MSL	
C. HOLE NO. 14 (shown on drawing sheet and site number)				12. MANUFACTURER'S DESIGNATION OF DRILL	PORTADRILL Model 524-T	
D. NAME OF DRILLER <u>MIKE SCHUBERT</u>				13. TOTAL NO. OF OVER DISTURBED	14. TOTAL NUMBER CORE BOXES	UNDISTURBED
E. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED DEG. FROM VERT.				BURDEN SAMPLES TAKEN	N/A	N/A
F. THICKNESS OF ONSURDEN 45.0				15. ELEVATION GROUND WATER		
G. DEPTH DRILLED INTO ROCK 15.7'				16. DATE HOLE STARTED Nov. 2 78	COMPLETED NOV. 2, 78	
H. TOTAL DEPTH OF HOLE 60.7				17. ELEVATION TOP OF HOLE 360.0		
				18. TOTAL CORE RECOVERY FOR BORING 72		
				19. SIGNATURE OF INSPECTOR <u>John M. Nale</u> <u>Green A. Chastain</u>		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOV. BY	BOX OR SAMPLE NO.	REMARKS (Drilling time, tools used, depth of overburden, etc., if significant)
360.0	0.0	.	TOP Casing	0	1	
			OVB Ht 10' log @ about 12.0'			
315.0	45.0		CLAYEY SHALE, bl.-gr m.h. slabby bkn 315.0 to 315.1 low l pa 314.3 to 314.2 v. frac. 314.3 to 314.0 low l pa. 313.6 to 313.5 low l pa. 312.2 to 312.1 low l pa. 311.9 to 311.8 v. frac. tij 312.2 to 311.4 low l pa 311.2 to 311.1	100	49.6	TOP Rock
318.3	46.0	SH	Core bk @ 310.4			
319.3	47.0	SH	low l pa's @ 310.1, 309.9 309.7, 309.6, 309.4			
312.2	48.0		sl. silted p n @ 308.6			
311.4	49.0		Clay bl.gr. soft. plastic			
308.6	51.0		SHALE h. bkn / soft + very friable matrix indicated			
308.2	51.8	clay				
308.2	52.0					
306.5	52.0	SH				
306.5	53.0					
305.8	55.0					
305.3	55.7		Fresh partings 304.2, 303.6, 303.4, 302.8, 302.6, 301.6, 300.6, 300.0 299.7.	55.7		Driller overran space available in barrel 10.25' length to end of center barrel. One was so broken up in box that condition of instn rock could not be determined.
305.3	56.0					
	57.0	SH				
	58.0					
	59.0					
	60.0					
299.3	60.7		Bottom of Hole			

DACW 27-78-C-0076

Hole No. C-6A

DRILLING LOG			DIVISION	INSTALLATION	SHEET OF 1 SHEETS	
			CONSTRUCTION	ORLCID		
PROJECT EVANSVILLE FLOOD PROTECTION DELAWARE STREET PUMP PLANT					10. SIZE AND TYPE OF BIT 6" BY 6" G	
LOCATION (Coordinates or Station)					11. DAY FOR ELEVATION TAKEN (Year or Month)	
DRILLING AGENCY J. E. MOSKINS DRILLING INC.					12. MANUFACTURER'S DESIGNATION OF DRILL PORTADRILL Model 524T	
13. HOLE NO. (As shown on drilling log) and Site number			14. TOTAL NO. OF OVER- BURDEN SAMPLES TAKEN		15. DISTURBED UNDISTURBED	
16. NAME OF DRILLER MIKE SCHUBERT			17. TOTAL NUMBER CORE BOXES 3		18. ELEVATION GROUND WATER	
19. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED DEG. FROM VERT.			20. DATE HOLE STARTED 8 Nov.		COMPLETED 8 Nov. 78	
21. THICKNESS OF OVERTURDEN 45.3			22. ELEVATION TOP OF HOLE 360.0		23. TOTAL CORE RECOVERY FOR BORING 100%	
24. DEPTH DRILLED INTO ROCK 12.0			25. SIGNATURE OF INSPECTOR / Logged by <i>John Christman</i>			
26. TOTAL DEPTH OF HOLE 57.3						
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	3 CORE RECOVERED	BOX OR SAMPLE NO. 1	REMARKS (Drilling time, recovery, description of overburden, rock, signatures)
360.3	0.0	-	OVB Ht. 45.3 about 12.0'	-	-	Top of casing during 1st run 360.3 360.3. After first run top of casing dropped to 360.0
314.7	45.3	SH	TOP of Rock CLAYEY SHALE 4-5 gr 5 fm. h. Solid core 314.7 to 313.3 h. concr. 20 314.1 to 312.2 pa @ 313.3	-	-	M.D. 45.6 Corrected 45.3 Bridging dipping 5° E. 314.7 to 309.5
313.3	47	-	V frac open 313.3	-	-	Cut 5.0' Rec'd 4.0'
312.7	47.6	-	(h. concr 20 312.8 to 312.7) pa @ 312.7	-	-	
311.9	48	-	V. frac open 311.9 to 310.3 bottom by water moving through rock	-	-	
310.3	50	-	V. frac. top 310.3 5 fm. h. pa @ 310.0, 309.8	-	-	M.D. 49.5 Corrected 49.6 Started 6.0
309.5	50.6	-	h. 514.6 by concr 20 64 m. 309.7 to 309.5	-	-	C.D. 50.6 Corrected 50.3
309.5	51	-	sec below for description material 329.5 to 306.5	100%	-	
306.5	53.8	M.H.	S/1. sided pn 306.5 to 306.3 (18° dip) m.h. shale	-	-	5. Shale hi. frac 1/2 to m.h. soft plastic clay seams
304.8	55	SH	h. concr 20 305.7 to 305.6	-	-	Firm m.h. SHALE
304.8	56	-	occ. concr. incl. size 305.3 to 305.1	-	-	Cut 7.8' Rec'd 8.0' Gain 1.0'
302.7	57	-	Bottom of Hole.	-	-	M.D. 57.3 C.D. 56.3'
302.7	58	-	309.5 to 309.4 concr tabber 309.4 to 309.2 s. sh. 309.2 to 309.15 s. plastic cl. 309.15 to 309.0 s. sh. 309.0 to 308.7 s. plastic cl. 308.7 to 308.5 s. sh. 308.5 to 308.3 s. plastic cl. 308.3 to 308.0 s. sh. 308.0 to 307.8 s. plastic cl. 307.8 to 307.75 concr 20. 307.75 to 307.0 s. sh. 307.0 to 306.5 s. plastic cl. 45° to j.t. 307.8 to 307.5 45° to j.t. 307.4 to 307.0 part way thru 307.0	-	-	
302.7	59	-		-	-	

CONTR. NO. DACW27-78-C-0076

Hole No. C-7

DRILLING LOG		DIVISION CONSTRUCTION	INSTALLATION ORLCID	SHEET 1 OF 2 SHEETS		
PROJECT EVANSVILLE FLOOD PROTECTION DELAWARE STREET PUMP PLANT		10. SIZE AND TYPE OF BIT 6"				
LOCATION N. E. CORNER OF STRUCTURE		11. DAY/DUE FOR ELEVATION SURVEY TIME OF REC'D MSL				
DRAILING AGENCY E. HOSKINS DRILLING INC.		12. MANUFACTURER'S DESIGNATION OF DRILL PORTA DRILL				
4. HOLE NO. (As shown on drilling data and site number)		13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN DISTURBED N/A UNDISTURBED N/A				
5. NAME OF DRILLER MIKE SCHUBERT		14. TOTAL NUMBER CORE BOXES 3				
6. DIRECTION OF HOLE VERTICAL <input type="checkbox"/> INCLINED DEG. FROM VERT.		15. ELEVATION GROUND WATER				
7. THICKNESS OF OVERTBURDEN 45.4		16. DATE HOLE STARTED 23 Oct. 78 COMPLETED 23 Oct. 78				
8. DEPTH DRILLED INTO ROCK 19.5		17. ELEVATION TOP OF HOLE 360.0				
9. TOTAL DEPTH OF HOLE 59.9		18. TOTAL CORE RECOVERY FOR BORING 97.9				
ELEVATION 360.0	DEPTH 45.4	LEGEND SH	CLASSIFICATION OF MATERIALS (Description) TOP OF Casing	CORE RECOV. DRY	BOX OR SAMPLE NO.	REMARKS (Drilling time, temperature, state of weathering, etc., is signified)
			0.0 TO 19.0 Backfill 19.0 TO 45.3 OVB	*		Drilled to 45.0 set casing & cleaned hole. Measured depth 45.4' Prior to start of coring.
314.6 45.4	310.6 45.2	SH	TOP of Rock.	LOSS		Measured Depth Top firm rock 314.8
			SHALE CLAYEY Bl. gr. m.h.; 1/2A. SC(1/2") Ø 31.5 310.9 309.6 308.3	BOX 1		Cut 5.0 Rec'd 2.1 Left 2.6 Loss 0.3
310.2 49.8	50.0					
				BOX 2		Cut 9.5 Rec'd 12.1 Gain 2.6
305.2 54.8	55					
				BOX 3		
51						
52						
53						
54						
55						
56						
57						

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE	Hole No. C-7		
PROJECT EVANSVILLE FLOOD PROTECTION DELAWARE ST. PUMP PLANT ORLCD			360.0 Top Casing	Sheet 2 of 2 Sheets		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
	57.0	c		*	f	
	58.0				Box 3	
300.1	59.9		Bottom of Hole			Measured depth 59.9
						After drilling completed hole was reamed back to 330 EL.

DRILLING LOG				DIVISION CONSTRUCTION	INSTALLATION ORLCO	BLOCK 1 OF 1 SHEETS
PROJECT EVANSVILLE FIELD IN SECTION DELAWARE STREET PUMP HOUSE				10. SIZE AND TYPE OF BIT 6"		
LOCATION (Coordinate or Description) ENTER EAST SIDE OF STRUCTURE				11. DATUM FOR ELEVATION SHOWN (TIDE OR Mean)		
DRILLING AGENCY J.E. HOSKINS DRILLING INC.				12. MANUFACTURER'S DESIGNATION OF DRILL PORTA DRILL		
HOLE NO. (as shown on drawing sheet)				13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN DISTURBED N/A UNDISTURBED N/A		
NAME OF DRILLER MIKE SCHUBERT				14. TOTAL NUMBER CORE BOXES		
DIRECTION OF HOLE VERTICAL <input checked="" type="checkbox"/> INCLINED _____ DEG. FROM VERT.				15. ELEVATION GROUND WATER		
7. THICKNESS OF OVERTURDEN 45.0				16. DATE HOLE STARTED 27 Oct. COMPLETED 27 Oct. 78		
8. DEPTH DRILLED INTO ROCK 15.9'				17. ELEVATION TOP OF HOLE 360.0		
9. TOTAL DEPTH OF HOLE 60.9'				18. TOTAL CORE RECOVERY FOR BORING 97		
ELEVATION 360.0	DEPTH 0.0	LEGEND Top Casing	CLASSIFICATION OF MATERIALS (Description)	SCORE RECOVERY %	BOX OR SAMPLE NO. 1	REMARKS (Drilling time, sample box, depth of overburden, etc., if significant)
			OUB			Set 8" Casing
315.0	45.0		TOP of Rock			
	46.0		CLAYEY SHALE bl.gr. m.h.	lost.		lost + 0.5' at top. off run.
	47		SOLID CORE 315.0 to 309.9			Run #1 Cut + 5.1' Rec'd 3.4' 1.7'
	48	SH				lost + 0.5' left. 1.2'
	49				Box No 1	MD. 48.9
	309.9	54.0			49.9	
	51					
	52				Box No 2	
	53	53.5			52.5	Run #2 Cut + 10.3' Rec'd 11.5'
	54					Gain 1.2'
	55				Box No 3	Core stuck in barrel. 59.9 to 60.8 softens
	56		twisted agg soil mixt.			by exposure to water and left in barrel over rock end. Had to be discarded cut + barrel badly broken
	57				57.1	
	302.9	59.6				
	58				Box No 4	
	59					
	60	60.0				
	299.6	60.4				Measured Depth 60.4
Bottom of Hole						

CONTR. NO. DACW27-78-C-0076 Hole No. C-9

DRILLING LOG	CONSTRUCTION	INSTALLATION	SHEET OF 1 SHEETS
C. PROJECT EVANSVILLE FLOOD PROTECTION DELAWARE STREET PUMP PLANT		OPICD	
E. LOCATION (Coordinates or Station)		10. SIZE AND TYPE OF BIT 6" BX 6 1/8"	
F. DRILLING AGENCY J. F. HOSKINS DRILLING INC.		11. DAY ON WHICH ELEVATION SHOT WAS MADE MSL	
G. HOLE NO. (As shown on drawing sheet and box number)		12. MANUFACTURER'S DESIGNATION OF DRILL PORTADRILL 529 T	
H. NAME OF DRILLER MIKE SCHUBERT		13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN N/A DISTURBED N/A UNDISTURBED N/A	
I. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED DEG. FROM VERT.		14. TOTAL NUMBER CORE BOXED 3	
J. THICKNESS OF OVERTBURDEN 44.8'		15. ELEVATION GROUND WATER	
K. DEPTH DRILLED INTO ROCK 15.6'		16. DATE HOLE STARTED 6 NOV. 78 COMPLETED 6 NOV. 78	
L. TOTAL DEPTH OF HOLE 60.4'		17. ELEVATION TOP OF HOLE 359.6	
		18. TOTAL CORE RECOVERY FOR BORING 97%	
		19. SIGNATURE OF INSPECTOR Logged by John A. Christman	

ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	CORE RECOV-	BOX OR SAMPLE NO.	REMARKS (Drilling Head, tool used, cause of nonrecov., etc., if significant)
359.6	0.0		Top Casing	0	1	
314.8	44.8		0VB			
314.8	44.8		Top of Rock Clayey Shale, bl-gr m.h. PA @ 313.6	105		Loss attributed to spiral top of run.
460	SH		hi L jt. 313.6 to 313.3			
460			PA @ 312.6			Cut 5.0' Rec'd 2.6'
470			concr. 20.311.4 to 311.3			Loss 0.4' Left. 2.0'
480			PA @ 308.6			M.D. 47.8
49.0			solid core 308.6 to 304.5/ concr. incl. 6" centers	Box 1		
50.0			PA @ 304.3, 304.2,			T.D. 49.8
309.3	50.0			50.3		
51.0				Box 2		
52						
53						
54						
304.3	55					
303.9	55.7		1/8" soft clay coated low PA @ 303.9 to 303.8			
303.8	55.8		PA @ 301.7			
	56		3m gr. size concr. incl. 302.6 to 300.6			
	57					
	58					
300.3	59			Box 3		
300.2	60		SOFT CLAY plastic			

ONE POUND 1036 PREVIOUS EDITIONS ARE OBSOLETE.
MAR 71 (TRANSLUCENT)PROJECT EVANSVILLE
FLOOD PROTECTION

HOLE NO. C-9

DAGW 27-78-C-0076

Hole No. C-10

DRILLING LOG	DIVISION	INSTALLATION	SHEET / OF 1 SHEETS
PROJECT EVANSVILLE FLOOD PROTECTION DELAWARE STREET PUMP PLANT LOCATION (Coordinate or Section)		OPLCD	
(DRILLING AGENCY J. E. HOSKINS DRILLING INC.		10. SIZE AND TYPE OF BIT 6" 6V 67F"	
11. DAYUM FOR ELEVATION BORING (FEET OR METERS)			
12. MANUFACTURER'S DESIGNATION OF DRILL PORTADRILL Model 524-T			
13. TOTAL NO. OF OVER- BURDEN SAMPLES TAKEN		DISTURBED	UNDISTURBED
14. TOTAL NUMBER CORE BOXES		N/A	N/A
15. ELEVATION GROUND WATER			
16. DATE HOLE STARTED 9 NOV. 78		COMPLETED 9 NOV. 78	
17. ELEVATION TOP OF HOLE 360.1			
18. TOTAL CORE RECOVERY FOR BORING 97			
19. SIGNATURE OF INSPECTOR Togged by Foster A. Christmas			
ELEVATION 360.1	DEPTH 0.0	LEGEND	CLASSIFICATION OF MATERIALS (Description)
			% CORE RECOV- ERY
			BOX OR SAMPLE NO.
			REMARKS (Drilling time, water level, depth of overburden, etc., if significant)
OUB			
314.7	45.4	Top of Rock	
46		CLAYEY SHALE, bl-gr. m.h.	
47		concr. nod. 313.3 to 313.2	
312.3	48	ti. pn. thr core 312.4 to 312.1	
311.5	49	ti. pn. tn. core 312.1 to 312.0	
310.6	49.5	v. frac open 312.4 to 312.1 (Appears water has been moving thr. rock) bding pa's are dipping 15° from 314.7 to 310.6	
50		core stuck in barrel 310.6 to 306.2. unable to determine natural condition of core from 310.6 to 306.2	
51		Highly crumbled mech.	
52		51.1	
53		100%	
306.5	54	v. frac. ti. 306.2 to 305.5	
306.2	54	hor. pa's @ 305.5	
305.5	54	304.7	
55		303.7	
56		302.8	
57		302.6	
58		301.6	
59		301.1	
60		299.5	
299.2	60.9	Bottom of Hole	
Set 8' Casing drilling dip 15° from 314.7 to 310.6			
Cut 5.0' Reid 3.6' 1.4' Lost 0.5' Left 0.9'			
- M.D. 49.5			
C.D. 50.4 After 2.5 hours of work in trying to remove core from barrel 49.5 to 53.9 barrel was taken to shop and heated to remove core.			
- M.D. 49.5 C.D. 51.4 G. in 0.9'			
M.D.			
Hole grouted to 330 ft 9 Nov. 78			

Appendix VI

Caissons


Delaware Street


Pump Station

CAISSON FIELD REPORT

	Casing No.	Date	Elev. Top	Elev. Bot.	Shaft Dia.	Offset Plumb	Penetr. Rock	Total Depth	Conc. Strength	12 Casing	Rod Strength
1	F-8	6-18-79	331.0	312.07	5'-6"	4 3/4 W 3/4 W	3 3/4 S, 1"-S	2.7	19.0	4108	66"X19' 314.7
2	F-4	6-26-79	330.59	311.34	5'-6"	5" N	O.K.	3.0	19.25	5206	66"X19' 315.0
3	E-6	6-28-79	330.3	311.20	5'-6"	6" W	O.K.	3.0	19.0	3418	66"X19' 315.0
4	F-2	8-16-79	331.0	312.09	5'-6"	3" W	1 1/2 W	2.6	18.92	4091	66"X19' 314.7
5	D-1	8-20-79	330.0	311.77	5'-6"	2" N	1 1/2 W	2.5	18.25	3964	66"X17' 314.7
6	D-3	8-24-79	330.89	311.52	5'-6"	1 1/2 W	1 1/2 N	3.1	18.5	4354	66"X17' 314.7
7	B-7	8-27-79	331.9	311.54	5'-6"	1 1/2 W	1 1/2 N	3.5	19.0	3778	66"X19' 315.1
8	B-5	8-28-79	330.0	311.0	5'-6"	2" W	1" W	4.0	19.0	3572	66"X19' 315.0
9	A-5	8-30-79	331.0	311.0	5'-6"	2 1/2 W	1" W	4.2	19.0	4690	66"X19' 315.2
10	A-7	8-30-79	331.0	312.0	5'-6"	1 1/2 W	O.K.	2.8	19.0	4690	66"X19' 314.7
11	A-3	8-31-79	331.0	303.93	5'-6"	1" W	1 1/2 W	11.0	17.0	3773	66"X17' 314.7
12	A-1	9-4-79	331.0	311.24	5'-6"	1" N	1 1/2 W	3.5	17.0	3816	66"X17' 314.8
13	A-6	9-4-79	331.0	312.28	5'-6"	1" W	O.K.	3.7	19.7	4050	66"X19' 315.1
14	A-4	9-5-79	331.0	312.0	5'-6"	2" W	1 1/2 W	3.0	19.0	4516	66"X19' 315.0
15	F-7	9-6-79	329.0	309.74	5'-6"	1 1/2 W	1 1/2 W	5.1	19.25	4605	66"X19' 314.8
16	D-5	9-7-79	331.0	311.61	5'-6"	1" W	1 1/2 W	3.1	19.5	6076	66"X19' 314.7
17	A-2	9-7-79	331.0	303.22	5'-6"	1 1/2 W	1 1/2 N	11.6	22.9	6076	66"X19' 314.8
18	B-6	9-10-79	331.0	310.61	5'-6"	2" E	1 1/2 W	4.4	19.4	4315	66"X19' 315.0
19	B-4	9-11-79	331.0	304.87	5'-6"	2" N	O.K.	5.83	26.2	4439	66"X19' 314.7
20	F-5	9-11-79	331.0	311.6	5'-6"	1 1/2 W	O.K.	3.1	19.0	5005	66"X19' 314.7
21	B-2	9-12-79	330.0	311.6	5'-6"	1" N	1 1/2 W	3.4	18.5	5005	66"X17' 314.8
22	D-2	9-13-79	330.0	311.28	5'-6"	2" W	1 1/2 N	3.1	18.75	4692	66"X17' 314.4
23	E-7	9-13-79	331.0	311.64	5'-6"	4-6 N	1" W	3.1	20.25	4616	66"X19' 314.7
24	B-5	9-17-79	331.0	311.04	5'-6"	1" E	1" N	3.7	20.0	4828	66"X19' 314.7
25	E-1	9-18-79	331.0	311.03	5'-6"	1" W	2" W	3.7	20.0	5005	66"X19' 314.7

AS BUILT DRAWING






CASE DRILLING LOCATIONS

NOTE: C-10 & C-11
ARE TO BE DRILLED IN
SQUARE HOLE

15

COPY OF DRAWING



DRAWING MACHINES

માન્દુરી 29 જાનુઆરી, 1982

卷之三

卷之三

卷之三

Tractor

卷之三

卷之三

三

卷之三


三


三

3

卷之三

EL. 222.55 ±
TOP OF MILE
Bottom of Hole






Appendix VII


72" R.C.P. Influent


Delaware Street

Pump Station



① 339.35
339.11
339.36





Plat 45

ATE
ME
8